

SBC 201 Chapter 33 Safeguards During Construction — Group R-2 High-Rise Dimensional Requirements Matrix (2024)

1. Document metadata and use limitation

- **Project basis:** Riyadh, Saudi Arabia; Group R-2 residential high-rise; an occupied floor is stated to be more than 23 m above the relevant reference level.
- **Deliverable tier:** Project-use matrices in Sections 4–12 (design-check rows, not pasted inventory), plus a coverage summary and unresolved-source register. The full row inventory is not published.
- **Code/source basis:** SBC 201 (2024), Chapter 33, source file Reference\SBC 201 2024\source_reference\Chapter_33 – SAFEGUARDS DURING CONSTRUCTION.txt.
- **Extraction audit:** Skill extract. Project-use rows follow the chapter-extract row contract (noun-phrase checks, bold SI values, building-language triggers, named exceptions, check-specific actions). Internal inventory: **60** independently checkable numeric records (**54** Verified, **6** Verify source). Flattened Table 3306.1 is listed in the register and is not a design-release value.
- **Model:** Cursor Grok 4.6.
- **Prepared:** 2026-08-27.
- **Status:** Source-only architectural advisory matrix for design coordination. It is not a stamped compliance statement, construction-safety plan, SCD NOC, SBPS approval, legal opinion, or permission to construct.
- **Outbound-source rule:** No value in this matrix has been imported from Chapter 9, 11, 16 or 18, Section 905, 906 or 111.3, SBC 303, 701 or 801 (including SBC 801 Chapter 33 and Appendix B), commentary examples, bibliography years, or the existing chapter summary. Where Chapter 33 sends the user elsewhere, this matrix records the dependency without supplying the outbound value.

Scope and assumptions

1. Group R-2 and high-rise status are project statements, not independently verified classifications.
2. The exact Riyadh AHJ/permit pathway, project stage, fire-strategy status and SCD NOC status are unconfirmed; therefore this matrix does not conclude compliance.
3. Automatic sprinkler protection, mixed-use podium, storey count and construction type are unconfirmed. Chapter 33 does not branch on NFPA 13 versus 13R. Type I or II is treated as the expected tower path for 3313.4; Type III/IV/V fire-flow bands stay Conditional.
4. Occupied-building phasing, demolition of an existing structure, and combustible materials delivered to site are unconfirmed. Those branches select 3302, 3303, 3310.2, 3311.2 and 3313.2.
5. Table 3306.1 in the attached extract is concatenated HTML with a conflicting last-band protection type. No table cell is adopted. Numbered walkway, railing, barrier and covered-walkway dimensions in 3306.2–3306.7 remain usable once the table (or the AHJ) selects the protection type.
6. Commentary conversions (7200 Pa, 6 m, 3785 L/m) and commentary pointers (Section 1011, SBC 801 Appendix B, Appendix J) are not treated as code cells.

2. Legends

Applicability

Status	Meaning
Direct	Expected to govern the stated R-2 tower basis, subject to confirmed geometry and design data.
Conditional	Governs only when the stated feature, construction type, occupied-phasing, demolition or exception exists.
Not typical	Unrelated occupancy-only or two-story light-frame rule; omitted from this deliverable unless the gap register already opened that use.
External verification	Chapter 33 points to another section/code/standard, or OCR/AHJ must be confirmed first.

Source confidence

Status	Meaning
Verified	Requirement and any stated numeric value were checked against unambiguous mandatory Chapter 33 source text.
Verify source	OCR, flattened table, page-split, or footnote attachment is unresolved. Not a design-release value.

3. Project decision and gap register

Decision / gap	Current project basis	Why it controls Chapter 33 application	Required project action
Occupied vs vacant construction	Unconfirmed whether any existing R-2, podium or neighbouring occupied structure stays occupied during work	3302.1 and 3310.2 keep exits, structure, fire protection and sanitary safeguards live unless a numbered exception applies	Freeze a phasing drawing: occupied floors, substitute exits, and which fire systems remain in service
Construction type	Unconfirmed; high-rise R-2 typically Type I or II, not verified	3313.4 is the Type I/II water-supply path; 3313.3.1–3313.3.3 apply only to Type III, IV or V using combustible materials	Lock type of construction before sizing construction-phase hydrants beyond 3313.2 / 3313.5
Combustible materials on site	Unconfirmed cladding, formwork, packaging and finish stores	3313.2 requires 1900 L/m within 152 m as soon as combustible building materials arrive, including on Type I/II sites	Plot material laydown versus hydrants on the construction logistics plan
Fire separation distance	Unconfirmed by lot line	Selects the Type III/IV/V fire-flow band if that construction type is used	Dimension FSD on the site plan before relying on 3313.3
Standpipe / 905.3.1	High-rise expected to need standpipes; Chapter 9 values not imported	3311.1 and 3313.5 time the first standpipe and a 1900 L/m hydrant within 30 m of the FDC once construction exceeds 12 m	Coordinate the construction standpipe with the 3310.1 stair and the FDC hydrant
Table 3306.1 protection type	Flattened HTML; last band lists both Barrier and None	Chooses construction railings (3306.4), site barriers (3306.5) and/or covered walkways (3306.7)	Verify the published table before freezing hoarding; do not reconstruct from IBC memory
Demolition	Unconfirmed whether an existing building is demolished	3303, 3311.2 and demolition fire safety to SBC 801 Chapter 33 apply only if demolition occurs	Confirm demolition scope; do not drop vacant-lot, utility-cap or demolition-standpipe rows until that is closed
Excavation / adjoining buildings	Unconfirmed basement, shoring and neighbour setbacks	3304 slopes, 3306.9 street-line barriers, 3307 notice and retention-system design lock the plot	Civil/structural to issue excavation, retention and 10-day neighbour-notice programme
Sprinkler / mixed use / storeys	Occupied floor stated above 23 m; sprinkler basis unconfirmed	3312.1 blocks occupancy until a required sprinkler is tested and approved except as Section 111.3 allows	Fire engineer to lock Chapter 9; do not occupy on a temporary certificate without the 111.3 path

Decision / gap	Current project basis	Why it controls Chapter 33 application	Required project action
NOC / construction fire plan	SCD NOC and SBC 801 Chapter 33 operations unconfirmed	3302.3, 3303.7 and 3309.2 send construction/demolition fire operations to SBC 801	Engage the fire consultant for the construction fire-safety plan; do not import 801 values here

4. Scope and occupied-building safeguards

Cite	Component / check	Exact source requirement / value	Trigger / condition	Exceptions / branch	R-2 tower status	Design action	Source confidence
3301.1	Chapter construction-safety scope	This chapter governs safety during construction and protection of adjacent public and private properties	Construction or demolition of the building and adjoining property	None stated	Direct	Put Chapter 33 on the construction logistics and hoarding drawings, not only on the completed-building code sheet	Verified
3301.2	Equipment and material placement	Store and place construction equipment and materials so as not to endanger the public, workers or adjoining property for the duration of the project	Construction equipment or materials on or next to the plot	None stated	Direct	Show laydown, crane and skip locations clear of public ways, exits and adjoining structures	Verified
3301.2.1	Roof construction loads	Structural roof components shall support the roof-covering system and the material and equipment loads encountered during installation	Roof covering or reroofing installation	None stated	Conditional	Have the structural engineer confirm staging loads before stacking roof materials or equipment	Verified
3302.1	Occupied-building life-safety hold	Required exits, existing structural elements, fire protection devices and sanitary safeguards shall be maintained at all times during alterations, repairs or additions	Alteration, repair or addition while the building or a portion remains in use	Exception 1: adequate substitute provisions where the required element is itself being altered or repaired. Exception 2: maintenance not required where the existing building is not occupied	Conditional	On occupied-phasing drawings, keep each required exit and fire/sanitary device live or show the approved substitute	Verified
3302.2	Waste removal method	Remove waste so as to prevent injury or damage to persons, adjoining properties and public rights-of-way	Construction or demolition waste leaving the site	None stated	Direct	Specify enclosed chutes, covered skips and approved haul routes on the logistics plan	Verified
3302.3	Construction fire-safety companion	Fire safety during construction shall comply with this code and Chapter 33 of SBC 801	Construction operations	Numeric 801 criteria are not in this chapter	External verification	Name SBC 801 Chapter 33 on the construction fire plan; do not copy 801 values into this matrix	Verified
3305.1	Construction sanitary facilities	Provide sanitary facilities during construction, remodeling or demolition in accordance with SBC 701	Construction, remodeling or demolition activities	Numeric 701 fixture counts are not in this chapter	External verification	Show welfare facilities on the site plan and size them from SBC 701, not from this chapter	Verified

5. Demolition

Cite	Component / check	Exact source requirement / value	Trigger / condition	Exceptions / branch	R-2 tower status	Design action	Source confidence
3303.1	Demolition documents and schedule	Submit construction documents and a demolition schedule where the building official requires them. Do not start work until those documents or the schedule, or both, are approved	Demolition where the building official requires submittals	None stated	Conditional	Issue a demolition method statement and programme before site start if the AHJ asks for them	Verified
3303.2	Demolition pedestrian protection	Do not commence demolishing any building until pedestrian protection required by this chapter is in place	Demolition of any building	Protection type still depends on Table 3306.1, which is unresolved	Conditional	Install the verified hoarding/walkway before the first demolition activity	Verified
3303.3	Horizontal-exit substitution	Do not destroy a horizontal exit unless and until a substitute means of egress has been provided and approved	Demolition affecting a horizontal exit	Substitute egress requires building-official approval	Conditional	Keep party-wall exits usable, or obtain approval of the replacement route, before taking the wall down	Verified
3303.4	Vacant-lot restoration	Where a structure has been demolished or removed, fill and maintain the vacant lot to the existing grade or in accordance with the ordinances of the jurisdiction	Structure demolished or removed with no immediate rebuild occupying the grade	AHJ ordinances may set a different grade	Conditional	Restore grade to match adjoining ground unless the municipality states another profile	Verified
3303.5	Demolition water accumulation	Prevent accumulation of water or damage to any foundations on the premises or the adjoining property	Vacant or open demolition site	None stated	Conditional	Grade and drain the demolition plot so water cannot pond against this or neighbouring foundations	Verified
3303.6	Utility disconnection	Discontinue and cap service utility connections in accordance with approved rules and the applicable governing authority	Demolition of a served structure	Temporary retained services need separate AHJ permits (not quantified here)	Conditional	Coordinate cap-off certificates with each utility before demolition	Verified
3303.7	Demolition fire-safety companion	Fire safety during demolition shall comply with this code and Chapter 33 of SBC 801	Demolition operations	Numeric 801 criteria are not in this chapter	External verification	Add SBC 801 Chapter 33 to the demolition fire plan; do not import 801 blasting or demolition figures	Verified

6. Site work, excavation and fill

Cite	Component / check	Exact source requirement / value	Trigger / condition	Exceptions / branch	R-2 tower status	Design action	Source confidence
3304.1	Stump, root and formwork removal	Remove stumps and roots to not less than 300 mm below the ground surface in the building footprint. Remove in-ground or sill-to-ground wood forms before occupancy or use. Remove loose or casual wood from direct contact with the ground under the building before completion	Excavation or fill for the building	None stated	Direct	Note the 300 mm grubbing depth and formwork strip on foundation and completion checklists	Verified
3304.1.1	Permanent cut and fill slopes	Permanent fill and permanent excavation cut slopes shall be not steeper than one unit vertical in two units horizontal (50-percent slope)	Permanent fill or permanent excavation around the building	Cut slopes may be steeper only with a soil investigation report acceptable to the building official. The report path is not stated for fill	Direct	Draw finished and excavation slopes at 1:2 or flatter unless an accepted soils report justifies a steeper cut	Verified
3304.1.2	Surcharge and adjacent footings	Place no fill or other surcharge adjacent to a building unless that building can take the additional load. Underpin or otherwise protect existing footings or foundations affected by excavation against settlement and lateral movement	Fill, surcharge or excavation next to an existing structure	None stated	Direct	Keep stockpiles and plant off neighbouring foundations unless the structural engineer designs protection or underpinning	Verified
3304.1.3	Footings on adjacent slopes	For footings on adjacent slopes, see Chapter 18	Footings on or next to slopes	Chapter 18 values are not in this chapter	External verification	Send slope-footing geometry to the Chapter 18 structural criteria; do not invent setbacks here	Verified
3304.1.4	Fill supporting foundations	Fill used to support foundations shall comply with SBC 303 . Special inspection of compacted fill shall be in accordance with Section 1705.6	Structural fill under foundations	Compaction criteria are not published in this chapter	External verification	Specify SBC 303 fill and 1705.6 inspection on the geotechnical notes; do not copy those values here	Verified

7. Pedestrian protection trigger

Cite	Component / check	Exact source requirement / value	Trigger / condition	Exceptions / branch	R-2 tower status	Design action	Source confidence
3306.1	Pedestrian protection and signs	Protect pedestrians during construction, remodeling and demolition as required by this chapter and Table 3306.1. Provide signs to direct pedestrian traffic	Construction, remodeling or demolition affecting pedestrians	Table 3306.1 cell values are not adopted from this extract	External verification	Provide directional signs; hold the protection <i>type</i> until the published table is verified	Verified
Table 3306.1	Pedestrian protection type	No value adopted. Flattened HTML concatenates height of building, distance from construction to lot line and type of protection. Apparent bands include 2.4 m, 1500 mm , one-fourth / one-half of construction height, and types named construction railings, barrier, barrier and covered walkway, or none. The last “exceeding one-half the height” token lists both Barrier and None	Construction next to a lot line / public pedestrian route	Row pairing is unresolved; rowspan and the duplicated last band conflict	External verification	Do not select railing, barrier or covered walkway from this extract or from IBC memory; check the published table	Verify source
3306.3	Street directional barricade	Protect pedestrian traffic with a directional barricade where the walkway extends into the street, sized and built to direct vehicles away from the pedestrian path	Walkway projecting into the street	None stated	Conditional	Add a vehicle-facing barricade and traffic diversion where the temporary walkway occupies carriageway	Verified
3306.8	Pedestrian protection duration	Maintain required pedestrian protection in good order for as long as pedestrians are endangered. On completion, immediately remove walkways, debris and other obstructions and restore public property	Pedestrian protection required by this chapter	None stated	Direct	Keep hoarding on the programme until handover, then restore the public way	Verified

8. Walkway, railing, barrier and excavation enclosure

Cite	Component / check	Exact source requirement / value	Trigger / condition	Exceptions / branch	R-2 tower status	Design action	Source confidence
3306.2	Pedestrian walkway width and load	Provide a walkway in front of every construction and demolition site, and from an occupied-structure entrance or exit to a public way, of sufficient width but not less than 1.2 m , with a durable surface, accessible per Chapter 11 , designed for all imposed loads, live load not less than 7.2 kN/m²	Construction or demolition frontage, or occupied building needing a route to a public way	Governing authority may authorise the sidewalk to be fenced or closed. Chapter 11 geometry is not imported	Direct	Dimension a $\geq$ 1.2 m accessible temporary walkway at 7.2 kN/m² on the hoarding plan, or obtain AHJ closure of the sidewalk	Verified
3306.4	Construction railing height	Construction railings shall be not less than 1.05 m in height and sufficient to direct pedestrians around construction areas	Table 3306.1 (unverified) requires construction railings	Commentary guard/1015 notes are not adopted	Conditional	Once the table requires railings, set the rail at $\geq$ 1.05 m and use it to steer pedestrians off the works	Verified
3306.5	Site barrier height and length	Barriers shall be not less than 2.4 m in height, on the walkway side nearest the construction, for the entire length of the construction site. Protect openings with doors that are normally kept closed	Table 3306.1 (unverified) requires a barrier	None stated	Conditional	Once the table requires a barrier, draw a $\geq$ 2.4 m continuous screen on the construction side with self-closing site doors	Verified

Cite	Component / check	Exact source requirement / value	Trigger / condition	Exceptions / branch	R-2 tower status	Design action	Source confidence
3306.6	Prescriptive barrier assembly	Design barriers for Chapter 16 loads, or build them with 50 mm by 100 mm top and bottom plates; boards not less than 19 mm or wood structural panels not less than 6.4 mm ; exterior-type adhesive on wood structural panels; 6.4 mm or 23.8 mm panels with studs not more than 600 mm on center; 9.5 mm or 12.5 mm panels with studs not more than 1200 mm on center and a 50 mm by 100 mm mid-height stiffener where studs exceed 600 mm ; 15.9 mm or thicker panels spanning not more than 2400 mm	Barrier required and the prescriptive timber path is used	Engineered Chapter 16 path needs no these member sizes; Chapter 16 values are not imported	Conditional	Either engineer the hoarding to Chapter 16 or match this member schedule on the barrier detail	Verified
3306.7	Covered walkway height and load	Covered walkways shall have a clear height of not less than 2.4 m from floor to canopy, adequate lighting at all times, and a design live load of not less than 7.2 kN/m² for the entire structure	Table 3306.1 (unverified) requires a covered walkway	Exception: new light-frame construction not exceeding two stories above grade plane may use 3.6 kPa or the imposed load, whichever is greater, or a seven-item timber recipe not published in this matrix (not typical for this high-rise)	Conditional	If a covered walkway is required, keep 2.4 m clear height and 7.2 kN/m² on the canopy; do not take the two-story 3.6 kPa path for the tower	Verified
3306.9	Excavation street-line barrier	Every excavation 1.5 m or less from the street lot line shall be enclosed with a barrier not less than 1.8 m in height. More than 1.5 m from the street lot line, erect a barrier where the building official requires. Resist Chapter 16 wind pressure	Excavation on the plot	Distance > 1.5 m is building-official discretion. Chapter 16 wind values are not imported	Conditional	If the basement cut is within 1.5 m of the street lot line, enclose it with a $\geq$ 1.8 m wind-rated barrier	Verified

9. Adjoining property and public ways

Cite	Component / check	Exact source requirement / value	Trigger / condition	Exceptions / branch	R-2 tower status	Design action	Source confidence
3307.1	Adjoining-property protection	Protect adjoining public and private property during construction, remodeling and demolition, including footings, foundations, party walls, chimneys, skylights and roofs. Control water runoff and erosion	Work that can affect adjoining property	None stated	Direct	Show neighbour-protection, runoff and erosion control on the construction method statement	Verified
3307.1	Excavation neighbour notice	The person causing an excavation shall give written notice to owners of adjoining buildings that the excavation will be made and that those buildings should be protected, delivered not less than 10 days before the scheduled start	Excavation that can affect adjoining buildings	None stated	Conditional	Issue the 10-day written notice before excavation start and keep the proof on the Golden Thread	Verified
3307.2–3307.2.3	Excavation retention system	Where a retention system supports an excavation to protect adjacent structures, a registered design professional shall design vertical and lateral support; the design shall require monitoring of the system and adjacent structures for horizontal and vertical movement; remove or decommission elements only where backfill or the new structure provides adequate replacement support	Retention system used to protect adjacent structures	None stated	Conditional	Assign shoring to the RDP, specify movement monitoring, and do not strike props until replacement support is in	Verified
3308.1	Temporary public-property storage	Temporary use of streets or public property for storing or handling construction or demolition materials or equipment, and public protection, shall comply with the applicable governing authority and this chapter	Storage or handling on streets or public property	AHJ street-occupation rules are not in this chapter	Conditional	Obtain the municipality street-occupation permit before placing skips or plant in the public way	Verified
3308.1.1	Intersection and hydrant clearances	Do not place or store construction materials and equipment so as to obstruct fire hydrants, standpipes, fire or police alarm boxes, catch basins or manholes, nor within 6.1 m of a street intersection, nor so as to obstruct traffic-signal observation or public-transit loading platforms	Materials or equipment on or next to the public way	None stated	Direct	Keep a 6.1 m clear cone at intersections and keep hydrants, standpipes, alarms and manholes unobstructed on the logistics plan	Verified
3308.2	Utility-fixture access	Do not place materials, fences, sheds or other obstructions so as to block free approach to a fire hydrant, fire department connection, utility pole, manhole, fire alarm box or catch basin, or so as to interfere with gutter flow. Protect those fixtures but do not hide them from sight	Work near utility or fire fixtures	None stated	Direct	Keep FDCs, hydrants and manholes visible and approachable on every construction stage plan	Verified

10. Construction egress, extinguishers, standpipes and sprinklers

Cite	Component / check	Exact source requirement / value	Trigger / condition	Exceptions / branch	R-2 tower status	Design action	Source confidence
3309.1	Portable fire extinguishers	Provide not fewer than one approved portable fire extinguisher per Section 906 , sized for not less than ordinary hazard, at each stairway on all floor levels where combustible materials have accumulated, in every storage and construction shed, and additional extinguishers where special hazards exist (flammable and combustible liquids)	Structure under construction, alteration or demolition	Section 906 ratings are not imported	Direct	Place ordinary-hazard extinguishers at working-level stairs, in every shed, and at fuel/solvent stores	Verified
3309.2	Construction fire-hazard companion	Observe this code and SBC 801 to safeguard against fire hazards attendant upon construction operations	Construction operations	Numeric 801 criteria are not in this chapter	External verification	Cross-reference SBC 801 on hot-work and combustible-storage controls; do not copy 801 values here	Verified
3310.1	Construction stairway	Where construction exceeds 12 m in height above the lowest level of fire department vehicle access, provide a temporary or permanent stairway and extend it to within one floor of the highest point of construction having secured decking or flooring	Tower construction above 12 m (this high-rise basis)	Commentary Section 1011 geometry is not adopted	Direct	Keep a usable stair within one floor of the working deck once the frame passes 12 m above FD access	Verified
3310.2	Occupied means of egress	Maintain required means of egress at all times during construction, demolition, remodeling or alterations and additions	Occupied building or portion during the works	Exception: existing means of egress need not be maintained where approved temporary means of egress systems and facilities are provided	Conditional	Keep required exits open on occupied floors, or obtain approval of the temporary egress scheme before blocking them	Verified
3311.1	Construction standpipe	In buildings required to have standpipes by Section 905.3.1 , provide not fewer than one standpipe for use during construction, installed before construction exceeds 12 m above the lowest level of fire department vehicle access, with hose connections adjacent to 3310.1 stairways, extended to within one floor of the highest secured decking or flooring	Building that 905.3.1 will require standpipes (expected high-rise path)	905.3.1 thresholds are not imported	Direct	Install the first construction standpipe before 12 m , next to the construction stair, and raise it with the working deck	Verified
3311.2	Demolition standpipe	Maintain an existing standpipe operable for the fire department during demolition. Do not demolish it more than one floor below the floor being demolished	Building being demolished that contains a standpipe	None stated	Conditional	During demolition, keep the standpipe live to one floor below the working demolition floor	Verified
3311.3	Standpipe installation standard	Install standpipes in accordance with Chapter 9	Construction or demolition standpipes under 3311	Exception: temporary or permanent standpipes, with or without a water supply, are permitted if they conform to Section 905 as to capacity, outlets and materials. Those 905 figures are not imported	External verification	Specify Chapter 9 / Section 905 capacity, outlets and materials on the construction standpipe; do not invent pipe sizes here	Verified
3312.1	Sprinkler completion before occupancy	Where this code requires an automatic sprinkler system, do not occupy any portion until the installation has been tested and approved, except as provided in Section 111.3	Required sprinkler building (unconfirmed until Chapter 9 is locked)	Temporary occupancy only via 111.3; 111.3 terms are not imported	Conditional	Do not occupy floors until the required sprinkler is tested and approved, unless a 111.3 temporary occupancy is granted	Verified
3312.2	Sprinkler valve control	Only authorised personnel may operate sprinkler control valves, with notification of designated parties. Where valves are turned off and on to connect new segments, check them at the end of each work period to confirm protection is in service	Sprinkler being extended or isolated during construction	None stated	Conditional	Write a valve-isolation permit and an end-of-shift “system in service” check into the construction fire plan	Verified

11. Water supply for fire protection

Cite	Component / check	Exact source requirement / value	Trigger / condition	Exceptions / branch	R-2 tower status	Design action	Source confidence
3313.1	Construction fire-flow timing	Provide an approved temporary or permanent fire-protection water supply as soon as combustible building materials arrive on site, on commencement of vertical combustible construction, and on installation of a standpipe, per 3313.2 through 3313.5	Combustible materials on site, vertical combustible construction, or standpipe installation	Exception: the fire code official may reduce fire-flow for isolated rural or small-community buildings where full fire-flow is impractical. Commentary Appendix B 3785 L/m is not adopted	Direct	Make hydrant water available before combustibles, combustible vertical work, or the standpipe — do not wait for building completion	Verified
3313.2	Combustible-materials fire flow	When combustible building materials of the building under construction are delivered, provide a minimum fire flow of 1900 L/m from a hydrant within 152 m of those materials, measured along an approved fire apparatus access lane. Add hydrants if one cannot cover all such materials	Combustible building materials delivered to the site (including Type I/II cladding or stores)	None stated	Direct	Place hydrants so every combustible laydown is within 152 m along an approved fire-access lane at 1900 L/m	Verified

Cite	Component / check	Exact source requirement / value	Trigger / condition	Exceptions / branch	R-2 tower status	Design action	Source confidence
3313.3.1–3313.3.3	Type III–V vertical fire flow	Before vertical construction of Type III, IV or V buildings that use any combustible building materials, provide hydrants to deliver: fire separation less than 9 m from lot lines (adjacent property built or buildable) — 1900 L/m or the entire completed-building fire flow, whichever is greater; 9 m up to 18 m — 1900 L/m or 50 percent of that completed fire flow, whichever is greater; 18 m or greater — 1900 L/m	Type III, IV or V vertical construction with combustible materials	Completed-building fire-flow value is not in this chapter. Not the default Type I/II tower path	Conditional	Use this band only if the podium or a structure is Type III–V; otherwise keep 3313.4	Verified
3313.4	Type I/II vertical fire flow	If combustible building materials are delivered, provide water supply per 3313.2. Additional water supply for fire flow is not required before commencing vertical construction of Type I and II buildings	Type I or II construction (expected tower path)	3313.2 still applies the moment combustibles arrive	Direct	For a Type I/II tower, do not add extra fire flow solely to start vertical work; still meet 3313.2 when combustibles are on site	Verified
3313.5	Standpipe hydrant supply	Where a standpipe is required by 3311, provide a water supply of not less than 1900 L/m from a hydrant within 30 m of the fire department connection supplying the standpipe, regardless of combustibles, construction type or fire separation distance	Construction standpipe required by 3311	None stated	Direct	Locate a 1900 L/m hydrant within 30 m of the construction FDC before the standpipe is relied upon	Verified

12. Fire watch

Cite	Component / check	Exact source requirement / value	Trigger / condition	Exceptions / branch	R-2 tower status	Design action	Source confidence
3314.1	Nonworking-hours fire watch	Provide a fire watch during nonworking hours for construction that exceeds 12 m in height above the lowest adjacent grade at any point along the building perimeter, for new multistory construction with an aggregate area exceeding 4645 m² per story, or as required by the fire code official	Construction exceeding 12 m at the perimeter, or a new multistory floor exceeding 4645 m²	Fire code official may require a watch at other sizes	Direct	Programme a night/weekend fire watch once the perimeter height exceeds 12 m , and also if any story exceeds 4645 m²	Verified

13. Project-use controls

1. Use **Verified** rows for initial construction-logistics scoping after the row trigger is confirmed (occupied phasing, demolition, excavation, combustibles on site, construction type).
2. Treat every **Verify source** row as a design hold. Table 3306.1 cells are empty of adopted values; do not reconstruct protection type from IBC memory or from the chapter summary.
3. Do not import Chapter 9 / 905 / 906 ratings, Chapter 11 walkway geometry, Chapter 16 wind or live loads, Chapter 18 slope-footing rules, Section 111.3 temporary-occupancy terms, SBC 303 compaction, SBC 701 fixture counts, or SBC 801 Chapter 33 / Appendix B fire-flow figures into issued drawings from this matrix.
4. Do not adopt commentary **7200 Pa**, **6 m**, **3785 L/m**, Section 1011 stair geometry, or bibliography years as code cells.
5. Do not apply the 3306.7 two-story light-frame **3.6 kPa** / seven-item timber recipe to this high-rise tower.
6. Record occupied-phasing, hoarding type, hydrant locations and fire-watch decisions in the project Golden Thread; this matrix is not evidence of SCD NOC or stamped compliance.

14. Coverage summary

Internal inventory of the attached Chapter 33 extract (numbered code, exceptions, tables, footnotes; commentary excluded). Row-level records are not published.

- **Inventory scope:** numbered code, exceptions, tables, footnotes (commentary excluded)
- **Total independently checkable numeric records:** 60
- **Verified:** 54
- **Verify source:** 6

Counts by top-level section

Top-level section	Records
3301	0
3302	0
3303	0
3304	3
3305	0
3306	34
3307	1
3308	1
3309	1
3310	2

Top-level section	Records
3311	4
3312	0
3313	12
3314	2

Appended tables: Table 3306.1 contributes **6** Verify-source records (apparent protection-type rows). Numbered 3306 clauses contribute the remaining **28** of the 3306 total.

Coverage cross-check against SBC 201 Chapter 33 Safeguards During Construction (2024)_CS.md was topics-only: occupied-building phasing; pedestrian walkways/railings/barriers/covered walkways; Table 3306.1 mashed HTML; excavation/adjoining notice; construction hydrants, standpipes and fire watch. No CS.md value was copied into a matrix cell.

15. Unresolved-source register

Affected table / clause	Why unverified	Control note
Table 3306.1 (6 records)	Concatenated HTML (HEIGHT OF BUILDING...DISTANCE...TYPE OF PROTECTION...) with rowspan="4". Tokens name 2.4 m, 1500 mm , one-fourth / one-half height, construction railings, barrier, barrier and covered walkway, and none. The last "exceeding one-half the height of construction" fragment lists both Barrier and None	No table-cell value is adopted. Do not repair pairing from IBC memory or CS.md printed bands. Numbered 3306.4 / 3306.5 / 3306.7 dimensions may be used only after the published table (or the AHJ) selects the protection type